BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

MODIFIED SCHEDULE-B

NAME OF WORK: Improvements & Providing Drinking of Water Supply in Bagalagunte Ward No 14

Sl. No	Description of work	Unit	Qty	Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation 1.5m and above in width in hard rock by chiselling and/or wedging, where blasting is prohibited for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m. in depth stacking the excavated stuff clear from the edge of excavation with lead upto 50m including cost of labour ccomplete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	401.22	1341.00	Rupees One Thousand Three Hundred Forty One Only
2	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. ccomplete as per specifications and as per the direction of Engineer-in-charge of the work.	m	1486.00	234.96	Rupees Two Hundred Thirty Four and Ninety Six Paise Only
3	Refilling the basement and pipeline trenches with selected available earth from trench excavation including watering, Consolidation in layers of 15 cm thick including disposing of the surplus earth with all lead & lifts..ccomplete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	401.22	116.91	Rupees One Hundred Sixteen and Ninety One Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

gnature of the Contractor

Executive Engineer

Scanned by CamScanner